



Flood & Storm Readiness Checklist

Restore Solutions – Printable Field Guide

Use this checklist before a storm, cyclone, or flood event to ensure your restoration team is fully prepared.

1. Equipment & Tools

- ☐ Dehumidifiers inspected (coils, cords, drainage)
- ☐ Dehumidifier coils cleaned
- ☐ Dehumidifiers tested for correct amp draw
- ☐ Air movers/axial fans cleaned, tagged, and tested
- ☐ HEPA air cleaners inspected: check seals and pre-filters
- ☐ HEPA filters replaced or cleaned
- ☐ Carbon filters checked/replaced
- ☐ Moisture meters calibrated and battery-checked
- ☐ Thermal imaging camera tested and cleaned
- ☐ Wet/dry vacuums inspected and filters cleaned
- ☐ Portable extractors tested (seals, hoses, pumps, suction)
- ☐ Portable extractor motors and brushes vacuumed
- ☐ Portable extraction tools cleaned
- ☐ Heat drying systems (Drymatic) tested; sensors checked
- ☐ Heat drying system heaters cleaned for dust and debris with compressed air
- ☐ Extension leads/RCDs tested and tagged
- ☐ Generators tested under load; fuel available
- ☐ Work lights checked and functioning

CREATING HEALTHY INDOOR ENVIRONMENTS

"On The Job" Industry Experience Since 1995





2. PPE & Safety

- ☐ P2 respirators (with carbon option) stocked
- ☐ P2 respirator masks is clean
- ☐ P2 respirator filters checked
- ☐ Nitrile gloves & chemical-resistant gloves stocked
- ☐ Disposable overalls with hoods available
- ☐ Boot covers available
- ☐ Waterproof boots ready
- ☐ Safety glasses/goggles available
- ☐ First-aid kits stocked

3. Antimicrobials (Protox Range)

- ☐ Protox Hysan – mould cleaner/remover & disinfectant
- ☐ Protox WR20 – antimicrobial cleaner for structural materials
- ☐ Protox DES – surface disinfectant
- ☐ SDS sheets printed and accessible

4. Consumables

- ☐ Microfibre cloths (bulk supply)
- ☐ Gloria sprayers (tested/pressurised)
- ☐ Containment plastic (200µm)
- ☐ Zippers, tape, and fixings for containment
- ☐ Heavy-duty rubbish bags/liners
- ☐ Floor protection film
- ☐ Rags, scrapers, sponges

CREATING HEALTHY INDOOR ENVIRONMENTS

"On The Job" Industry Experience Since 1995





5. Documentation & Standards

- ☐ Moisture meters calibrated (date recorded)
- ☐ Baseline psychrometric forms prepared
- ☐ Daily GPP tracking sheets printed
- ☐ Photo documentation process ready (cameras/tablets charged)
- ☐ Printed job sheets prepared for network outages
- ☐ Staff reminders on AS-IICRC S500 drying procedures

6. Warehouse & Logistics

- ☐ All equipment raised off floor level
- ☐ Warehouse drainage and seals checked
- ☐ Radios/tablets/meters fully charged
- ☐ Transport crates labelled and staged
- ☐ Spare consumable kits assembled
- ☐ Fuel supply on-site for generators/vehicles

7. Vehicles & Deployment

- ☐ Vehicles fully fuelled
- ☐ Tyres, lights, wipers, batteries checked
- ☐ PPE and essential tools pre-loaded in one response vehicle
- ☐ Maps/routes checked for flood risks
- ☐ Communication devices charged

Final Check

- Team briefed on deployment plan
- Safety procedures reviewed
- Contact numbers for management and suppliers confirmed

Restore Solutions – 0411 800 983 or 0411 501 931

This checklist is designed for rapid review and printing before severe weather events.

CREATING HEALTHY INDOOR ENVIRONMENTS

"On The Job" Industry Experience Since 1995

